STAFF REPORT
WEST ALLIS PLAN COMMISSION
Wednesday, September 24, 2025
6:00 PM

2A. Conditional Use Permit for SoNa Lofts Phase 2, Lot 3, a proposed 5+ Unit Dwelling, at 1600 S. 66th St.

2B. Site, Landscaping, and Architectural Design Review for SoNa Lofts Phase 2, Lot 3, a proposed 5+ Unit Dwelling, at 1600 S. 66th St. (Tax Key No. 454-0656-000).

Overview and Zoning

SoNa Lofts Phase II, Lot 3, buildings upon the success of Phase 1 with an additional residential building on the currently vacant parcel at 1600 S. 66th St. The project proposed 66 units with associated structured and surface parking, clubhouse amenities, and activated ground floor retail.

Mandel Group anticipates construction duration to be an estimated 15 months.

Q1 2026 – Commence Construction
Q2 2027 – Building Occupancy

1600 S. 66th St. is zoned C-3. 5+ Unit Dwellings require Conditional Use Permits in the C-3 zoning district. While a Conditional Use Permit has been approved for the Lot 4 development along Mitchell St., this is a separate development that will require a Conditional Use Permit of its own.

Certified Survey Map

Mandel Group indicated that they would be pursuing a certified survey map to combine the currently separated parcels at 1600 S. 66th St (Lot 3) and 6600 W. Mitchell St. (Lot 4) to assist with a future creation of a Tax Increment Financing district that will impact the two projects. Plan Commissions consideration for the combination of the two parcels is necessary for the project's development.



Site Plan

The existing site is currently vacant, serving largely as an area for overflow parking for the West Allis Farmers Market. Proposed on the site is a 4-5 story mixed-use building with 66 units, 37 underground parking stalls, 38 surface stalls, and a ground-floor retail space at the northeast corner of the building near Makers Row. A community clubhouse anchors this building with resident amenities including a spa, wellness lounge, fitness area, and coworking space. Entrance to the site is provided in a manner of ways. Access to a shared parking lot with SoNa Lofts Phase I is provided currently off of S 66th St, W. Mitchell St., and W. National Ave. This proposal calls for an extension of that existing parking area to provide surface parking along the rear of the proposed building. Underground parking is accessed via a garage entrance along S. 66th St. In addition to the parking area are connecting pedestrian walkways, providing a campus-esque pedestrian experience across the multiple Mandel projects in the area.



Landscaping Plan

The proposed development will include a variety of natural features meant to complement the existing and future landscaping of the other SoNa projects.

The site will be densely landscaped along the building. A variety of deciduous and evergreen shrubs will line the perimeter of the building. Flowering trees, ornamental grasses, and perennials will create a visual buffer between the parking area and the proposed building. Additionally,

A mix of trees will also provide a buffer between the public sidewalk on S 66th St. and the eastern side of the building.

During a meeting with staff, the applicant mentioned an alteration of the submitted landscaping plan. Staff will need to review the landscaping plan to ensure compliance with City Forestry standards.



Architectural Plan

The architect of the project, Rinka, recently met with staff regarding several comments that arose during internal staff review. During that meeting, staff was able to view changes to the initial architectural elevations. At the time the staff report was written, only the east elevation's updates were captured. Rinka will provide more details on the architecture of the project at the Plan Commission meeting. An overview of the architecture by staff is provided below.

The building's eastern street facing façade is comprised of stack bond brick, primarily in a dark grey color. For visual interest the architect has included an alternate shade of brick found above and below the numerous fiberglass windows. This shade of brick also makes up vertical elements that visually separates the building into three sections. Balconies along this façade provide visual interest and activation. The façade is further activated through street level glazing for the future retail tenant space. A canopy for the retail user wraps its way around to the northern elevation.

The north elevation of the building continues the use of the stack bond brick. The narrow northern elevation is broken into two sections by a vertical wood-look fiber cement panel. In place of brick, the separated side intends to utilize a dark colored fiber cement panel along the 2nd-4th floors. The first floor shows an abundance of glazing, adding to the activation of this façade. Moving further west along the north elevation brings forth the proposed clubhouse amenity. Paying homage to historic industrial architecture, the clubhouse's notable feature is the use of colored glass working from the floor to the beginning of the gabled roof. In addition to this glass is exposed metal truss along with weathered steel. The overall clubhouse maintains this look on the west and south elevations.

The apartment building's west elevation is comprised of the dark colored fiber cement material, stretching across the 2nd-4th floors. The first floor utilizes the wood-look fiber cement panel. A variety of windows work their way across the west elevation.

Similar to the north elevation, the south elevation is comprised of the two sections of dark fiber cement and stack bond brick, with the wood-look panel running vertically.

3 NORTH ELEVATION



3 CLUBHOUSE - WEST ELEVATION
1/8" = 1'-0"

CLUBHOUSE - SOUTH ELEVATION
1/8" = 1'-0"



2 CLUBHOUSE - NORTH ELEVATION
1/8" = 1'-0"



Floor Plan

Parking makes up the entirety of the below ground floor. Drivers will access this parking garage by an entrance to the garage on the eastern side of the building. The first floor consists of 15 apartment units along with a dog wash station, lobby, and clubhouse amenities including a hot tub, cold plunge, sauna, wellness lounge, and fitness center. The second, third, fourth floors consist of apartments with nearly identical layouts, each featuring 17 apartment units each.



Unit Mix
A unit mix has not yet been provided but the applicant has stated intent on discussing this matter further. As indicated by the applicant, a majority of units will be 1 bedroom.

Parking
SoNa Lofts Phase 2, Lot 3 will include 75 total parking stalls, a ratio of 1.14 stalls per unit. This parking ratio is inline with other apartment developments within the City. This is below the maximum requirement of 132 stalls (2 per unit). 37 indoor bicycle parking spaces, a total of 13 is required per code. 4 outdoor bicycle racks are shown on site. A total of 3 are required per code.

Design Guidelines

Compliance with the design guidelines is mandatory for new development. The proposed project satisfies all applicable guideline requirements. Highlights include:

1. Context
    a. Neighbor: Higher density scale is appropriate for site in major area. Material and style references to historic industrial area. Strong focus on pedestrian connectivity through and around site, improves access for an area with history of poor pedestrian design.
2. Public Realm
    a. Active Ground Floor: strong blending of public and private realm and activating public realm with townhome private entries/patios along the private drive. Townhomes and mural prevent blank first floor walls.
    b. Build for People: Pedestrian pathways and internal connections are provided next to a natural feature, a rarity in the direct neighborhood.
    c. Mitigate Impacts: vehicle parking primarily enclosed within building, also shielded from public realm.
3. Quality
    a. Building: high-quality building with compelling design, quality material palette, and unique points of emphasis.
    b. Environment: focus on integrating natural features. Reduction in impervious surfaces and inclusion of a bioretention pond. Increased density promotes reductions in energy use per capita.

See attached Plan Commission checklist.

Recommendation: Approve the Site, Landscaping, and Architectural Design Review for SoNa Lofts Phase 2, Lot 3, a proposed 5+ Unit Dwelling, at 1600 S. 66th St. (Tax Key No. 454-0656-000).

1. Common Council approval of the conditional use (scheduled October 7, 2025).
2. A Certified Survey Map being submitted to the Planning & Zoning office with subsequent Common Council approval of the Certified Survey Map subject to technical corrections.
3. Revised Site, Landscaping, and Architectural plans submitted to show the following: a) The provision of one EV charging station in the parking plan; b) Updated elevations to reflect the enhanced architectural details of the overall building, and commercial space; (d) a revised landscaping plan subject to City Forester review and approval;

4. Documentation and approval showing compliance with the City of West Allis Stormwater Management Ordinance, to be submitted to the Building Inspections and Neighborhood Services Department by a registered Civil Engineer. A stormwater permit must be obtained from the City Building Inspector. Contact Mike Romens, Building Inspector, at 414-302-8413.
5. Coordination with WeEnergies and preparation of an estimated cost of overhead wires being relocated/placed underground. Of note, staff is not recommending Plan Commission require overhead wires being placed underground, but is recommending that the concept be explored further.
6. Signage and site lighting plan being submitted for design review.

MANDEL GROUP

SoNa Phase II
Site, Landscaping and Architectural Amendment
August 2025

Description of Building Improvements

Since the original submission of the SoNa Phase II plans, we have refined the vision by redesigning the Lot 4 building and introducing a second residential building on Lot 3, ensuring the project better reflects the needs of the local market. Drawing on insights from the success of The West Living and SoNa Lofts, we now have a clear understanding of residents' needs and recognize the void SoNa Phase II can fill. These updated plans build upon and improve the original submission from November 2023, ensuring a thoughtful and market-responsive approach:

Lot 3
A dynamic 4–5 story building with an overall height of approximately 57 feet includes partially exposed underground parking of 37 stalls in addition to 38 surface stalls. The ground floor will feature an activated corner retail space near Makers Row, bringing energy and walkability to the streetscape, alongside 15 residential units. Above, three levels will each consist of 17 units, bringing the total to 66 new homes. Adding to the vibrancy, Lot 3 will include a dedicated clubhouse serving the entire SoNa community, complete with an impressive array of amenities—clubroom, expansive patio, state-of-the-art fitness center, wellness lounge, and a relaxing outdoor spa—offering residents a truly elevated living experience.

Lot 4
A four-story building with an overall height of approximately 44 feet, this building features a convenient 57 parking stalls (27 underground + 30 surface) paired with six inviting walk-up residences, bringing life and accessibility right to the street. There will be three residential floors above which each include15 homes, yielding 51 units in total. This building will offer residences well-conceived to reflect the character of the neighborhood while enhancing the overall SoNa community.

The buildings are designed with clean, floating volumes anchored by prominent masonry forms that unify the composition. Altogether, the vision brings forward a total of 117 new residences across the two buildings, thoughtfully designed to activate the street, complement the surrounding neighborhood, and elevate the SoNa living experience. Rooted in the design language of the existing development with a mix of walk-ups, upper-level homes, ground-floor retail, and exceptional community amenities, this proposal reflects an exciting step forward in creating a vibrant, connected, and highly desirable place to call home.

Timeline

Construction duration is estimated to be 15 months.

Q1 2026 – Commence Construction
Q2 2027 – Building Occupancy

Description of Operations + Services

Designed with today's residents in mind, the property will feature a clubroom, expansive patio, state-of-the-art fitness center, wellness lounge, and a relaxing outdoor spa and both indoor and outdoor parking. With an intentional blend of comfort and convenience, SoNa Phase II will offer the very best in contemporary living.

The community will be professionally managed by Mandel Property Services, Inc., renowned for delivering exceptional service across Mandel Group's portfolio of luxury apartment communities. Residents can expect the same high standard of care and attention that defines the Mandel experience, as we continue our tradition of excellence while enhancing the sustainability and livability of SoNa Phase II.

Days + Hours of Operation

Leasing Office:

Monday through Friday from 9:00 a.m. to 5:00 p.m.

Saturday from 9:00 a.m. to 2:00 p.m.

SoNa LOFTS - PHASE 2

[redacted] W MITCHELL ST. & 66TH ST. WEST ALLIS, WI 53214 [redacted]

PLAN COMMISSION

ISSUE DATE - 08/29/2025

SHEET INDEX

ARCHITECTURAL

TITLE	TITLE SHEET AND PROJECT INFORMATION
0000	ARCHITECTURAL SITE PLAN
0001	LOT 3 - LEVEL B1 FLOOR PLAN
0002	LOT 3 - LEVEL 01 FLOOR PLAN
0003	LOT 3 - TYPICAL FLOOR PLAN 2-4
0004	LOT 3 - BUILDING ELEVATIONS
0005	LOT 3 - BUILDING ELEVATIONS
0006	LOT 3 - PERSPECTIVE
0007	CLUBHOUSE - PERSPECTIVE
0008	LOT 4 - LEVEL 01 FLOOR PLAN
0009	LOT 4 - TYPICAL FLOOR PLAN 2-4
0010	LOT 4 - BUILDING ELEVATIONS
0011	LOT 4 - PERSPECTIVE

LOT 3 - CIVIL / LANDSCAPING / SITE LIGHTING

C-1	SITE PLAN
C-2	GRADING & SPOT GRADE PLAN
C-3	UTILITY PLAN
C-4	CONSTRUCTION DETAILS & SPECIFICATIONS
L-1	LANDSCAPE PLAN
L-2	LANDSCAPE GENERAL NOTES & DETAILS
	LIGHTING LAYOUT

LOT 4 - CIVIL / LANDSCAPING / SITE LIGHTING

C-1	SITE PLAN
C-2	GRADING & EROSION CONTROL PLAN
C-3	UTILITY PLAN
C-4	CONSTRUCTION DETAILS & SPECIFICATIONS
L-1	LANDSCAPE PLAN
L-2	LANDSCAPE GENERAL NOTES & DETAILS
	LIGHTING LAYOUT

ARCHITECT
RINKA INC.
756 N MILWAUKEE STREET
SUITE 250
MILWAUKEE, WI 53202
(414) 431-8101

OWNER
MANDEL GROUP
330 E KILBOURN AVENUE
MILWAUKEE, WI 53202
(414) 347-3600

CIVIL & LANDSCAPE ENGINEER
PINNACLE ENGINEERING GROUP
20725 WATERTOWN ROAD
WAUKESHA, WI 53186
(262) 754-8888

CONCEPTUAL RENDERING - LOT 3

CONCEPTUAL RENDERING - LOT 4

VICINITY MAP

N

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

TITLE SHEET AND PROJECT INFORMATION

Sheet # TITLE



ARCHITECTURAL SITE PLAN
1" = 30'-0"

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

ARCHITECTURAL SITE PLAN

Sheet #
0000



1 LEVEL B1 FLOOR PLAN
3/32" = 1'-0"

True North

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS -
PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LOT 3 - LEVEL B1
FLOOR PLAN

Sheet #
0001

1 LEVEL 01 FLOOR PLAN
3/32" = 1'-0"

True North

©2025 RINKA+

RINKA+
756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LOT 3 - LEVEL 01 FLOOR PLAN

Sheet # 0002

NOT FOR CONSTRUCTION



2 LEVEL 03-04 FLOOR PLAN
3/32" = 1'-0"



1 LEVEL 02 FLOOR PLAN
3/32" = 1'-0"

True North

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

Revisions

PLAN COMMISSION

SoNa LOFTS -
PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LOT 3 - TYPICAL
FLOOR PLAN 2-4

Sheet #
0003

NOT FOR CONSTRUCTION



3 NORTH ELEVATION
1/8" = 1'-0"

2 WEST ELEVATION
1/8" = 1'-0"

1 EAST ELEVATION
1/8" = 1'-0"

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074
Sheet Title

LOT 3 - BUILDING ELEVATIONS

Sheet # 0004

3 LOT 3 - NORTH ELEVATION
1/8" = 1'-0"

2 LOT 3 - WEST ELEVATION
1/8" = 1'-0"

1 LOT 3 - EAST ELEVATION
1/8" = 1'-0"

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 09/24/2025

RINKA project #: 25074

Sheet Title

LOT 3 - BUILDING ELEVATIONS

Sheet # 0004

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202



3 CLUBHOUSE - WEST ELEVATION
1/8" = 1'-0"



4 CLUBHOUSE - SOUTH ELEVATION
1/8" = 1'-0"

2 CLUBHOUSE - NORTH ELEVATION
1/8" = 1'-0"

1 SOUTH ELEVATION
1/8" = 1'-0"

NOT FOR CONSTRUCTION

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LOT 3 - BUILDING ELEVATIONS

Sheet # 0005

NOT FOR CONSTRUCTION

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LOT 3 - PERSPECTIVE

Sheet # 0006

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

MANDEL GROUP
330 E Kilbourn Ave,
Milwaukee, Wisconsin 53202

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

CLUBHOUSE - PERSPECTIVE

Sheet # 0007

NOT FOR CONSTRUCTION



LEGEND

- SANITARY SEWER MANHOLE
- STORM SEWER MANHOLE
- STORM SEWER CATCH BASIN (ROUND CASTING)
- STORM SEWER CATCH BASIN (RECTANGULAR CASTING)
- CLEANOUT
- VALVE BOX
- FIRE HYDRANT
- SANITARY SEWER
- STORM SEWER
- WATER MAIN
- ELECTRICAL CABLE
- GAS MAIN
- TELEPHONE LINE
- OVERHEAD WIRES
- LIGHTING
- ELECTRICAL TRANSFORMER OR PEDESTAL

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

PINNACLE ENGINEERING GROUP
ENGINEERING | NATURAL RESOURCES | SURVEYING
WISCONSIN OFFICE:
20725 W. WATERTOWN ROAD
BROOKFIELD, WI 53186
(262) 754-8888

NOT FOR CONSTRUCTION

THESE DRAWINGS ARE RELEASED FOR DESIGN DEVELOPMENT PURPOSES ONLY. THEY ARE NOT TO BE USE FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION PURPOSES .

△ Revisions

PLAN COMMISSION

SoNa LOFTS - PHASE 2

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

UTILITY PLAN

Sheet # C-3

GENERAL SPECIFICATIONS FOR CONSTRUCTION ACTIVITIES

1. THE PROPOSED IMPROVEMENTS SHALL BE CONSTRUCTED ACCORDING TO THE WISCONSIN D.O.T. STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION, LATEST EDITION, THE STANDARD SPECIFICATIONS FOR SEWER & WATER IN WISCONSIN, AND WISCONSIN ADMINISTRATIVE CODE, SPS 360, 382-383, AND THE LOCAL ORDINANCES AND SPECIFICATIONS.
2. THE CONTRACTOR SHALL OBTAIN ALL PERMITS REQUIRED FOR EXECUTION OF THE WORK. THE CONTRACTOR SHALL CONDUCT HIS WORK ACCORDING TO THE REQUIREMENTS OF THE PERMITS.
3. THE CONTRACTOR SHALL NOTIFY THE OWNER AND THE MUNICIPALITY FORTY- EIGHT (48) HOURS PRIOR TO THE START OF CONSTRUCTION.
4. THE MUNICIPALITY SHALL HAVE THE RIGHT TO INSPECT, APPROVE, AND REJECT THE CONSTRUCTION OF THE PUBLIC PORTIONS OF THE WORK. THE OWNER SHALL HAVE THE RIGHT TO INSPECT, APPROVE, AND REJECT THE CONSTRUCTION OF ALL PRIVATE PORTIONS OF THE WORK.
5. THE CONTRACTOR SHALL INDEMNIFY THE OWNER, THE ENGINEER, AND THE MUNICIPALITY, THEIR AGENTS, ETC, FROM ALL LIABILITY INVOLVED WITH THE CONSTRUCTION, INSTALLATION, AND TESTING OF THE WORK ON THIS PROJECT.
6. SITE SAFETY SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
7. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL UTILITY INFORMATION SHOWN ON THE PLANS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL CALL DIGGER'S HOTLINE AT 1-800-242-8511 TO NOTIFY THE UTILITIES OF HIS INTENTIONS, AND TO REQUEST FIELD STAKING OF EXISTING UTILITIES.
8. SILT FENCE AND OTHER EROSION CONTROL FACILITIES MUST BE INSTALLED PRIOR TO CONSTRUCTION OR ANY OTHER LAND DISTURBING ACTIVITY. FOLLOW THE SEQUENCE OF CONSTRUCTION ON THE EROSION CONTROL PLAN FOR MORE DETAILS. INSPECTIONS SHALL BE MADE WEEKLY OR AFTER EVERY RAINFALL OF 0.5" OR MORE. REPAIRS SHALL BE MADE IMMEDIATELY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL EROSION CONTROL FACILITIES ONCE THE THREAT OF EROSION HAS PASSED WITH THE APPROVAL OF THE GOVERNING AGENCY.
9. ANY ADJACENT PROPERTIES OR ROAD RIGHT-OF-WAYS WHICH ARE DAMAGED DURING CONSTRUCTION MUST BE RESTORED BY THE CONTRACTOR.
10. TRASH AND DEBRIS SHALL BE NOT BE ALLOWED TO ACCUMULATE ON THIS SITE AND THE SITE SHALL BE CLEAN UPON COMPLETION OF WORK.
11. THE OWNER SHALL HAVE THE RIGHT TO HAVE ALL MATERIALS USED IN CONSTRUCTION TESTED FOR COMPLIANCE WITH THESE SPECIFICATIONS.

SPECIFICATIONS FOR GRADING & EROSION CONTROL

1. EARTHWORK FOR SITE ONLY- REFER TO ***31 00 00 - EARTHWORK BUILDING*** IN THE MASTER SPECIFICATIONS FOR REQUIREMENTS UNDER STRUCTURES.
2. THE CONTRACTOR SHALL ASSUME SOLE RESPONSIBILITY FOR THE COMPUTATIONS OF ALL GRADING AND FOR ACTUAL LAND BALANCE, INCLUDING UTILITY TRENCH SPOIL. THE CONTRACTOR SHALL IMPORT OR EXPORT MATERIAL AS NECESSARY TO COMPLETE THE PROJECT. CONTRACTOR SHALL NOTIFY OWNER OF THE NEED TO IMPORT OR HAUL OFF SOIL. ON-SITE LOCATIONS SUITABLE FOR BORROW OR FILL MAY BE PRESENT. COORDINATE WITH OWNER.
3. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING SOIL CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION. A GEOTECHNICAL REPORT MAY BE AVAILABLE FROM THE OWNER.
4. SITE SHALL BE CLEARED TO THE LIMITS SHOWN ON THE PLANS. REMOVE VEGETATION FROM THE SITE. BURNING IS NOT PERMITTED. PROTECT TREES AND OTHER FEATURES FROM DAMAGE WITH FENCING. STOCKPILES SHALL NOT BE LOCATED CLOSER THAN 25' TO A DRAINAGE STRUCTURE OR FEATURE AND SHALL BE SURROUNDED WITH SILT FENCE.
5. THE GEOTECHNICAL ENGINEER IS RESPONSIBLE FOR VERIFYING COMPACTION AND FILL PLACEMENT IN THE FIELD. THE GEOTECHNICAL ENGINEER MAY SUPERCEDE THESE SPECIFICATIONS IF THERE IS GOOD CAUSE TO DO SO. AN EXPLANATION MUST BE SUBMITTED TO THE ENGINEER IN WITTING BEFORE ANY DEVIATIONS ARE MADE.
6. IF NO GEOTECHNICAL RECOMMENDATION IS AVAILABLE, THEN THE FOLLOWING SPECIFICATIONS SHALL APPLY. ALL FILL SHALL BE CONSIDERED STRUCTURAL FILL AND SHALL BE PLACED IN ACCORDANCE WITH THE FOLLOWING: THE COMPACTED FILL SUBGRADE SHALL CONSIST OF AND SHALL BE UNDERLAIN BY SUITABLE BEARING MATERIALS, FREE OF ALL ORGANIC, FROZEN OR OTHER DELETERIOUS MATERIAL AND INSPECTED AND APPROVED BY THE RESIDENT GEOTECHNICAL ENGINEER. PREPARATION OF THE SUBGRADE, AFTER STRIPPING, SHALL CONSIST OF PROOF-ROLLING TO DETECT UNSTABLE AREAS THAT MIGHT BE UNDERCUT, AND COMPACTING THE SCARIFIED SURFACE TO THE SAME MINIMUM DENSITY INDICATED BELOW. THE COMPACTED FILL MATERIALS SHALL BE FREE OF ANY DELETERIOUS, ORGANIC OR FROZEN MATTER AND SHALL HAVE A MAXIMUM LIQUID LIMIT (ASTM-D-4243) IF 30 AND 10 RESPECTFULLY, UNLESS SPECIFICALLY TESTED AND FOUND TO HAVE LOW EXPANSIVE PROPERTIES AND APPROVED BY AN EXPERIENCED SOILS ENGINEER. THE TOP TWELVE (12") INCHES OF COMPACTED FILL SHOULD HAVE A MAXIMUM THREE (3") INCH PARTICLE DIAMETER AND ALL UNDERLYING COMPACTED FILL A MAXIMUM SIX (6") INCH PARTICLE DIAMETER UNLESS SPECIFICALLY APPROVED BY AN EXPERIENCED SOILS ENGINEER. ALL FILL MATERIAL MUST BE TESTED AND APPROVED UNDER THE DIRECTION AND SUPERVISION OF AN EXPERIENCED SOILS ENGINEER PRIOR TO PLACEMENT. IF THE FILL IS TO PROVIDE NON-FROST SUSCEPTIBLE CHARACTERISTICS, IT MUST BE CLASSIFIED AS A CLEAN GW, GP, SW, OR SP PER UNITED SOIL CLASSIFICATION SYSTEM (ASTM D-2487). FOR STRUCTURAL FILL THE DENSITY OF THE STRUCTURAL COMPACTED FILL AND SCARIFIED SUBGRADE AND GRADES SHALL NOT BE LESS THAN 95 PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE STANDARD PROCTOR (ASTM D-698) WITH THE EXCEPTION TO THE TOP 12 INCHES OF PAVEMENT SUBGRADE WHICH SHALL A MINIMUM IN-SITU DENSITY OF 100 PERCENT OF THE MAXIMUM DRY DENSITY, OR 5 PERCENT HIGHER THAN UNDERLYING FILL MATERIALS. THE MOISTURE CONTENT OF COHESIVE SOIL SHALL NOT VARY BY MORE THAN -1 TO +3 PERCENT AND GRANULAR SOIL ±3 PERCENT OF OPTIMUM WHEN PLACED AND COMPACTED OR RECOMPACTED, UNLESS OTHERWISE RECOMMENDED BY THE SOILS ENGINEER TAKING INTO CONSIDERATION THE TYPE OF MATERIALS AND COMPACTION EQUIPMENT BEING USED. THE COMPACTION EQUIPMENT SHOULD CONSIST OF SUITABLE MECHANICAL EQUIPMENT SPECIFICALLY DESIGNED FOR SOIL COMPACTION. BULLDOZERS OR SIMILAR TRACKED VEHICLES ARE TYPICALLY NOT SUITABLE FOR COMPACTION. MATERIAL THAT IS TOO WET TO PERMIT PROPER COMPACTION MAY BE SPREAD ON THE FILL AND PERMITTED TO DRY. DISCING, HARROWING OR PULVERIZING MAY BE NECESSARY TO REDUCE THE MOISTURE CONTENT TO A SATISFACTORY VALUE, AFTER WHICH IT SHALL BE COMPACTED. THE FINISHED SUBGRADE AREAS OF THE SITE SHALL BE COMPACTED TO 100 PERCENT OF THE STANDARD PROCTOR (ASTM D-398) MAXIMUM DENSITY.
7. NO FILL SHALL BE PLACED ON A WET OR SOFT SUBGRADE. THE SUBGRADE SHALL BE PROOF-ROLLED AND INSPECTED BY THE GEOTECHNICAL ENGINEER BEFORE ANY MATERIAL IS PLACED.
8. SUBGRADE TOLERANCES ARE +/-1" FOR LANDSCAPE AREAS AND +/- ½" FOR ALL PAVEMENT AND BUILDING AREAS.
9. TOPSOIL SHALL BE FREE OF DELETERIOUS MATERIALS, ROOTS, OLD VEGETATION, ROCKS OVER 2" DIAMETER AND SHALL NOT BE EXCESSIVELY CLAYEY IN NATURE, NO CLUMPS LARGER THAN 4" ARE ACCEPTABLE. TOPSOIL MAY BE AMENDED AS NEEDED WITH SAND OR COMPOST TO BE LOOSE WHEN SPREAD.
10. THE CONTRACTOR SHALL MAINTAIN SITE DRAINAGE THROUGHOUT CONSTRUCTION. THIS MAY INCLUDE THE EXCAVATION OF TEMPORARY DITCHES OR PUMPING TO ALLEVIATE WATER PONDING. ANY DEWATERING SHALL NOT GO DIRECTLY TO STREAMS, CREEKS, WETLANDS OR OTHER ENVIRONMENTALLY SENSITIVE AREAS WITHOUT BEING TREATED FIRST. A DIRT BAG OR OTHER DEWATERING TREATMENT DEVICE MAY BE USED TO CAPTURE SEDIMENT FROM THE PUMPED WATER.
11. CONTRACTOR IS ADVISED THAT ALL MUD AND DEBRIS MUST NOT BE DEPOSITED ONTO THE ADJACENT ROADWAYS PER THE REQUIREMENT OF THE MUNICIPALITY OR OTHER APPROPRIATE GOVERNMENT AGENCIES. IN THE EVENT THIS OCCURS, THE ROADWAYS SHALL BE POWER SWEPT IMMEDIATELY AND ALL SEDIMENT REMOVED FROM DOWNSTREAM FACILITIES.

SPECIFICATIONS FOR PRIVATE UTILITIES

1. BEFORE PROCEEDING WITH ANY UTILITY CONSTRUCTION, THE CONTRACTOR SHALL EXCAVATE EACH EXISTING LATERAL OR POINT OF CONNECTION AND VERIFY THE LOCATION AND ELEVATION OF ALL UTILITIES. IF ANY EXISTING UTILITIES ARE NOT AS SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY FOR POSSIBLE REDESIGN.
2. ALL CONNECTIONS TO EXISTING PIPES AND MANHOLES SHALL BE CORED CONNECTIONS. CONNECTIONS TO WATERMAIN SHALL BE WET TAPED WITH A STAINLESS STEEP TAPPING SLEEVE.
3. PROPOSED SANITARY SEWER AND INTERNALLY CONNECTED STORM SEWER SHOWN ON THIS PLAN SHALL TERMINATE AT A POINT FIVE (5) FEET FROM THE EXTERIOR BUILDING WALL. THE EXACT LOCATION OF ALL DOWN SPOUTS CONNECTIONS SHALL BE PER THE ARCHITECTURAL PLANS.
4. CONTRACTOR SHALL NOT SHUT OFF WATER OR PLUG SANITARY SEWER IN MUNICIPAL LINES WITHOUT PRIOR APPROVAL.
5. MATERIALS FOR STORM SEWER SHALL BE AS FOLLOWS: STORM SEWER PIPE 48" OR LESS SHALL BE HIGH DENSITY POLYETHYLENE (HDPE) CORRUGATED PIPE WITH AN INTEGRALLY FORMED SMOOTH WATERWAY SUCH AS ADS N-12, FOR PIPE 10" OR LESS IN DIAMETER, PVC, ASTM D-3034, SDR-26, MAY ALSO BE USED. WHERE SPECIFICALLY REQUIRED, REINFORCED CONCRETE PIPE (RCP), ASTM C-76, CLASS III OR HIGHER, MAY BE USED. TRENCH SECTION SHALL BE CLASS "B" FOR PVC AND HDPE AND CLASS "C" FOR CONCRETE (PER STANDARD SPECIFICATIONS). MANHOLES, INLETS AND CATCH BASINS SHALL BE PRE CAST REINFORCED CONCRETE, ASTM C-478. HEAVY DUTY CAST IRON AREA DRAINS SHALL BE PER THE DETAIL ON THE PLANS. CONNECTIONS TO EXISTING PIPES SHALL BE MADE WITH INSERTA WYE OR EQUIVALENT. LAST (3) THREE JOINTS SHALL BE RESTRAINED WITH RODS.
6. MATERIALS FOR SANITARY SEWER SHALL BE AS FOLLOWS: SANITARY SEWER SHALL BE PVC, ASTM D-3034, SDR-35 WITH RUBBER GASKETED JOINTS, CONFORMING TO ASTM D-3212. TRENCH SECTIONS SHALL BE CLASS "B" BEDDING (PER STANDARD SPECIFICATIONS). CRUSHED STONE CHIPS SHALL BE USED FOR BEDDING MATERIAL. CONNECTIONS SHALL BE MADE WITH A WET TAP. CORPORATE STOP AND VALVE BOX PER MUNICIPAL STANDARDS. A MINIMUM OF 6' COVER IS REQUIRED FOR ALL WATERMAIN. VALVES SHALL BE NONRISING STEM, RESILIENT SEATED GATE VALVES COMPLYING WITH AWWA C509 WITH A THREE PIECE CAST IRON VALVE BOX. INSTALL THRUST BLOCKS AT ALL BENDS AND TEES. DISINFECT ALL NEW LINES AND OBTAIN SAFE WATER SAMPLE PRIOR TO USE.
7. EXTREME CAUTION MUST BE FOLLOWED REGARDING THE COMPACTION OF ALL UTILITY TRENCHES. MECHANICALLY COMPACTED GRANULAR BACKFILL IS REQUIRED UNDER & WITHIN 5 FEET OF ALL PAVEMENT INCLUDING SIDEWALKS. FLOODING OF BACKFILL MATERIAL IS NOT ALLOWED.
8. TRACER WIRE (NO. 8 SINGLE STRAND COPPER) AND WARNING TAPE SHALL BE INSTALLED ON ALL UTILITIES IN ACCORDANCE WITH THE LOCAL AND STATE CODES. TRACER WIRE SHALL TERMINATE IN A VALVECO TERMINAL BOX AT EACH END.
9. MANDREL TESTING ON SANITARY LINES AND PRESSURE TESTING ON WATERMAIN MAY BE REQUIRED BY THE OWNER OR MUNICIPALITY.
10. UPON COMPLETION OF FINAL PAVING OPERATIONS, THE UTILITY CONTRACTOR SHALL ADJUST ALL MANHOLE AND INLET RIMS AND VALVE BOXES TO FINISHED GRADE.

SPECIFICATIONS FOR PAVING

1. AGGREGATES USED IN THE CRUSHED STONE BASE SHALL CONFORM TO THE GRADATION REQUIREMENTS SECTIONS 301.2 AND 305.2.2 OF THE STANDARD SPECIFICATIONS. THICKNESS SHALL BE PER THE DETAIL ON THE PLANS. BASE SHALL BE 1 ½ INCH DIAMETER LIMESTONE TRAFFIC BOND AGGREGATE BASE COURSE UNLESS NOTED OTHERWISE. SUBSTITUTION AND/OR RECYCLED MATERIALS MAY BE ALLOWED WITH APPROVAL FROM THE OWNER.
2. SUBGRADE SHALL BE PROOFROLLED AND APPROVED BY A GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT OF STONE BASE. EXCAVATE UNSUITABLE AREAS AND REPLACE WITH BREAKER RUN STONE AND RECOMPACT. REFER TO THE GEOTECHNICAL REPORT FOR ADDITIONAL SPECIFICATIONS.
3. EXISTING PAVEMENT SHALL BE SAWCUT IN NEAT STRAIGHT LINES TO FULL DEPTH AT ANY POINT WHERE EXISTING PAVEMENT IS REMOVED. CURB AND WALK SHALL BE REMOVED TO THE NEAREST JOINT. REMOVED PAVEMENT SHALL BE REPLACED WITH THE SAME SECTION AS EXISTING. MUNICIPAL STANDARDS MAY REQUIRE ADDITIONAL WORK.
4. ASPHALT FOR PARKING AREAS AND THE PRIVATE ROAD SHALL BE PER THE DETAILS MATERIALS AND PLACEMENT SHALL CONFORM TO THE DOT STANDARD SPECIFICATIONS, SECTION 450 AND 460 LT 58-28 S IS REQUIRED UNLESS NOTED OTHERWISE. A COMMERCIAL GRADE MIX MAY BE SUBSTITUTED ONLY WITH APPROVAL FROM THE OWNER.
5. CONCRETE FOR CURB, DRIVEWAY, WALKS AND NON-FLOOR SLABS SHALL CONFORM TO SECTION 415 OF THE STANDARD SPECIFICATIONS , GRADE A, ASTM C-94, 6 BAG MIX, WITH A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3,500 PSI. JOINTING SHALL BE PER SECTION 415.3.7 OF THE STANDARD SPECIFICATIONS WITH CONSTRUCTION JOINTS HAVING A MAXIMUM SPACING OF 10'. EXPANSION JOINTS SHALL BE PROVIDED EVERY 50'. CONCRETE SHALL BE FINISHED PER SECTION 415.3.8 WITH A MEDIUM BROOM TEXTURE. A CURING MEMBRANE IN CONFORMANCE WITH SECTION 415.3.12 IS REQUIRED.



TRENCH DETAIL

NOTES:

1. ALL SILT FENCE MATERIALS AND INSTALLATION SHALL BE IN CONFORMANCE WITH WI DNR TECHNICAL STANDARD 1056.
2. GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592 GEOTEXTILE TABLE 1 OR 2, CLASS I WITH EQUIVALENT OPENING SIZE OF AT LEAST 30 FOR NONWOVEN AND 50 FOR WOVEN.
3. SILT FENCE SHALL BE ANCHORED BY SPREADING AT LEAST 8-INCHES OF FABRIC IN A 4-INCH WIDE AND 4-INCH DEEP TRENCH OR 8-INCH DEEP V-TRENCH ON THE UPSLOPE SIDE OF THE FENCE. TRENCHES SHALL NOT BE EXCAVATED WIDER OR DEEPER THAN NECESSARY FOR PROPER INSTALLATION.
4. FOLD MATERIAL TO FIT TRENCH AND BACKFILL AND COMPACT TRENCH WITH EXCAVATED SOIL.
5. WOOD POSTS SHALL BE A MINIMUM SIZE OF 1.125-INCHES x 1.125-INCHES OF DRIED OAK OR HICKORY.
6. SILT FENCE TO EXTEND ABOVE THE TOP OF PIPE, WHERE APPLICABLE.
7. POST SPACING SHALL BE SELECTED BASED ON GEOTEXTILE FABRIC (8-FEET FOR WOVEN AND 3-FEET FOR NON-WOVEN).

SILT FENCE



NOTES:

1. INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.
2. MANUFACTURED ALTERNATIVES NOT APPROVED AND LISTED ON THE WisDOT EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED.
3. WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

① FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10 INCHES AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.

② FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2 INCH X 4 INCH.

INSTALLATION NOTES:

1. DO NOT INSTALL INLET PROTECTION TYPE "D" IN INLETS SHALLOWER THAN 30 INCHES, MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.
2. TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3 INCHES OF THE GRATE.
3. THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3 INCHES. WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3 INCHES CLEARANCE. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4 INCHES FROM THE BOTTOM OF THE BAG.

INLET PROTECTION



NOTES:

1. ALL TRACKING PAD MATERIALS AND INSTALLATION SHALL BE IN CONFORMANCE WITH WI DNR TECHNICAL STANDARD 1057.
2. TRACKING PADS SHALL BE INSTALLED PRIOR TO ANY TRAFFIC LEAVING THE SITE. CONTRACTOR SHALL VERIFY LOCATION WITH OWNER.
3. THE AGGREGATE FOR TRACKING PADS SHALL BE 3 TO 6 INCH CLEAR OR WASHED STONE, ALL MATERIALS TO BE RETAINED ON A 3-INCH SIEVE
4. THE AGGREGATE SHALL BE PLACED IN A LAYER AT LEAST 12-INCHES THICK. ON SITES WHERE SATURATED CONDITIONS ARE EXPECTED DURING THE LIFE OF THE PAD, THE PAD SHALL BE UNDERLAIN WITH GEOTEXTILE FABRIC WHICH MEETS MATERIAL SPECIFICATION 592 GEOTEXTILE, TABLE 1 OR 2, CLASS I, II OR IV, TO PREVENT MIGRATION OF UNDERLYING SOILS INTO THE STONE LAYER.
5. THE TRACKING PAD SHALL BE THE FULL WIDTH OF THE EGRESS POINT. MINIMUM WIDTH IS 14 FEET FOR ONE-WAY TRAFFIC AND 20 FEET FOR TWO-WAY TRAFFIC, WITH AN ADDITIONAL INCREASE OF 4 FEET FOR TRAILER TRAFFIC. THE TRACKING PAD SHALL BE A MINIMUM 50-FEET LONG.
6. ANY SEDIMENT TRACKED ONTO A PUBLIC OR PRIVATE ROAD SHOULD BE REMOVED BY STREET CLEANING, NOT FLUSHING, AT THE END OF EACH WORKING DAY.
7. TRACKING PADS SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24-HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5-INCHES OF RAIN OR MORE DURING A 24-HOUR PERIOD.
8. THE TRACKING PAD PERFORMANCE SHALL BE MAINTAINED BY SCRAPING OR TOP-DRESSING WITH ADDITIONAL AGGREGATE.

CONSTRUCTION ENTRANCE



1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" (15 CM) DEEP X 6" (15 CM). WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE BLANKET.
3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTAL ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM , STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" - 5" (5 CM - 12.5 CM) OVERLAP DEPENDING ON BLANKET TYPE.
5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE BLANKET WIDTH.

NOTE: "IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

EROSION MATTING - SLOPE INSTALLATION



1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE BLANKET IN A 6" (15 CM) DEEP X 6" (15 CM). WIDE TRENCH WITH APPROXIMATELY 12" (30 CM) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE BLANKET.
3. ROLL CENTER BLANKETS IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM , STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. PLACE CONSECUTIVE BLANKETS END OVER END (SHINGLE STYLE) WITH A 4" - 6" (10 CM-15 CM) OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER TO SECURE BLANKETS.
5. FULL LENGTH EDGE OF BLANKETS AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
6. ADJACENT BLANKETS MUST BE OVERLAPPED APPROXIMATELY 3" - 4" (7.5 CM -12.5 CM) DEPENDING ON BLANKET TYPE) AND STAPLED.
7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 M - 12 M) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.
8. THE TERMINAL END OF THE BLANKETS MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

NOTE: "IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY ANCHOR THE BLANKETS.

EROSION MATTING - CHANNEL INSTALLATION



AREA DRAIN



DOWNSPOUT DRAIN BUILDING CONNECTION



NOTES:

1. EASY STICK, RUBBER GASKET OR APPROVED EQUIVALENT SHALL BE PLACED AT ALL JOINTS BETWEEN ADJUSTING RINGS FOR STORM CATCH BASINS.
2. THE FLAT TOP MAY BE USED IN LIEU OF THE T



PLANT SCHEDULE

CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
DECIDUOUS TREES					
QE	2	Quercus x `Crimschmidt`	Crimson Spire™ Oak	2.5" Cal.	45' T x 15' W
UAV	3	Ulmus americana 'Valley Forge'	Valley Forge Elm	2.5" Cal.	80' T x 60' W
EVERGREEN TREES					
JT	10	Juniperus chinensis 'Trautman'	Trautman Juniper	5` Ht.	12' T x 4' W
JX	4	Juniperus x 'J.N Select Blue'	Star Power® Juniper	5` Ht.	17' T x 8' W
TGG	3	Thuja occidentalis 'Green Giant'	Green Giant Arborvitae	5` Ht.	50` T x 15` W
ORNAMENTAL TREES					
AGA	1	Amelanchier x grandiflora 'Autumn Brilliance'	Autumn Brilliance Serviceberry	1.5" Cal.	20' T x 20' W
SRS	5	Syringa reticulata 'Summer Storm'	Summer Storm Tree Lilac	1.5" Cal.	17' T x 12' W
DECIDUOUS SHRUBS					
CH	2	Cercis canadensis 'Hearts of Gold'	Hearts of Gold Eastern Redbud	7 gal.	14' T x 14' W
VR	60	Diervilla rivularis `SMNDRSF`	Kodiak® Black Honeysuckle	1.5` Ht.	4' T x 4' W
HBO	24	Hydrangea paniculata `Bobo`	Bobo Hydrangea	1.5` Ht.	3' T x 3' W
HL	3	Hydrangea paniculata 'Limelight'	Limelight Panicle Hydrangea	5 gal.	
RAG	3	Rhus aromatica `Gro-Low`	Gro-Low Fragrant Sumac	1.5` Ht.	2' T x 7' W
RTE	5	Rhus typhina `Tiger Eyes`	Tiger Eyes Sumac	3 gal.	5' T x 5' W
EVERGREEN SHRUBS					
JSG	22	Juniperus chinensis `Sea Green`	Sea Green Juniper	1.5` Ht.	5` T x 6` W
TTE	11	Thuja occidentalis `BailJohn`	Technito Arborvitae	4` Ht.	12` T x 5 `W
THH	3	Thuja occidentalis `Holmstrup`	Holmstrup Cedar	4` Ht.	12` T x 3` W
TFC	10	Thuja occidentalis 'Congabe'	Fire Chief Arborvitae	1.5` Ht.	2' T x 3' W
ORNAMENTAL GRASSES					
CFO	54	Calamagrostis x a `Overdam`	Overdam Reed Grass	1 gal.	24" T x 24" W
MSO	37	Miscanthus sinensis `Oktoberfest`	Oktoberfest Miscanthus	1 gal.	48" T x 36" W

CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING	REMARKS
PERENNIALS						
AH	179	Amsonia hubrichtii	Arkansas Bluestar	1 gal.	24" o.c.	24" T x 24" W
EE	64	Echinacea x 'PAS702917'	PowWow® Wild Berry Coneflower	1 gal.	18" o.c.	18" T x 15" W
PF	22	Phlox x 'Forever Pink'	Forever Pink Phlox	1 gal.	18" o.c.	12" T x 12" W
SM	62	Sedum x 'Matrona'	Matrona Sedum	1 gal.	20" o.c.	20" T x 20" W

SYMBOL	QTY	BOTANICAL NAME	COMMON NAME	REMARKS
TURF				
	3,685 sf	Turf Hydroseed	Reinders - Cadet 70/30 Fescue/Blue Mix	

REFERENCE NOTES SCHEDULE

SYMBOL	CODE	DESCRIPTION	QTY	DETAIL
	1	STONE MULCH- 3/4 ROUND RAPIDS, #8940 RED ROCK GRANITE	847 sf	8/L-2

©2025 RINKA+

756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

△ Revisions

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LANDSCAPE PLAN

Sheet # L-1

GENERAL PLANTING NOTES

1. THE LAYOUT OF ALL PLANTING BEDS AND INDIVIDUAL TREES AND SHRUBS SHALL BE STAKED BY THE CONTRACTOR IN ADVANCE OF INSTALLATION. FLAGGING, STAKES, OR PAINT MAY BE USED TO DELINEATE LOCATIONS AS SCALED FROM THE PLANS. AN APPROVED REPRESENTATIVE WILL REVIEW THESE LOCATIONS WITH THE CONTRACTOR AND MAKE MINOR ADJUSTMENTS AS NECESSARY. BED LAYOUT SHALL ALSO INCLUDE PERENNIAL GROUPINGS BY SPECIES.
2. THE CONTRACTOR IS RESPONSIBLE FOR INDEPENDENTLY DETERMINING THE PLANT MATERIAL QUANTITIES REQUIRED BY THE LANDSCAPE PLANS. REPORT ANY DISCREPANCIES TO THE LANDSCAPE ARCHITECT.
3. NO PLANT MATERIAL OR PLANT SIZE SUBSTITUTIONS WILL BE ACCEPTED WITHOUT APPROVAL BY THE LANDSCAPE ARCHITECT. ANY CHANGES SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT IN WRITING PRIOR TO INSTALLATION.
4. ALL BNB STOCK SHALL BE NURSERY GROWN IN A CLAY LOAM SOIL FOR A MINIMUM OF THREE GROWING SEASONS WITHIN 200 MILES OF PROJECT LOCATION, IN A ZONE COMPATIBLE WITH USDA HARDINESS ZONE 5A. SEED SHALL BE PROVIDED FROM A NURSERY (WITHIN 200 MILES) WITH A SIMILAR PLANT HARDINESS ZONE AS PROJECT LOCATION. EXISTING SOIL SHALL BE AMENDED PER SOIL ANALYSIS REPORT TO ENSURE A PROPER GROWING MEDIUM IS ACHIEVED.
5. ALL PLANT MATERIAL SHALL COMPLY WITH STANDARDS DESCRIBED IN AMERICAN STANDARD OF NURSERY STOCK - Z60.1 ANSI. LANDSCAPE ARCHITECT OR OWNERS AUTHORIZED REPRESENTATIVE RESERVES THE RIGHT TO INSPECT AND POTENTIALLY REJECT ANY PLANT MATERIAL DEEMED TO NOT MEET THE REQUIRED STANDARDS.
6. ALL STOCK SHALL BE FREE OF DISEASES AND HARMFUL INSECTS, DAMAGE, DISORDERS AND DEFORMITIES.
7. TREES SHALL HAVE SINGLE, STRAIGHT TRUNKS AND WELL BALANCED BRANCH SYSTEMS. MUTLI-STEM TREES SHALL HAVE 3-4 STRAIGHT TRUNKS AND WELL BALANCED BRANCH SYSTEMS. HEIGHT-TO-CALIPER RATIOS SHALL BE CONSISTENT WITH THE LATEST EDITION OF ANSI Z60.1.
8. ROOT SYSTEMS SHALL BE LARGE ENOUGH TO ALLOW FOR FULL RECOVERY OF THE TREE, AND SHALL CONFORM TO STANDARDS AS THEY APPEAR IN THE MOST CURRENT REVISION OF THE AMERICAN ASSOCIATION OF NURSERYMEN'S AMERICAN STANDARD OF NURSERY STOCK ANSI Z60.1.
9. BNB TREES SHALL BE DUG WITH A BALL OF SOIL, NOT SOFT BALLED OR POTTED AND SHALL BE FIRM IN THEIR ROOTBALL. ROOT BALL SHALL BE WRAPPED (WITH BIODEGRADABLE MATERIAL). THE TREE ROOT FLARE, OR COLLAR, SHALL BE AT OR WITHIN THE TOP THREE INCHES OF GRADE.
10. ALL SPRING TREES MUST BE FRESHLY DUG IN THE MOST RECENT SPRING.
11. ALL AUTUMN TREES MUST BE FRESHLY DUG IN THE MOST RECENT AUTUMN.
12. TREES SHALL BE ALIVE, HEALTHY AND APPROPRIATELY MOIST, AT TIME OF DELIVERY. TREES SHALL BE SUBJECT TO INSPECTION FOR CONFORMITY TO SPECIFICATION REQUIREMENTS AND APPROVAL BY THE LANDSCAPE ARCHITECT OR OWNERS REPRESENTATIVE. THE LANDSCAPE ARCHITECT OR OWNERS REPRESENTATIVE RESERVES THE RIGHT TO REJECT ANY TREES THAT DO NOT MEET THE SPECIFICATIONS OR THAT HAVE BEEN DAMAGED DURING SHIPMENT. THE LANDSCAPE INSTALLER MUST RECEIVE APPROVAL FROM LANDSCAPE ARCHITECT FOR ANY SUBSTITUTIONS OR ALTERATIONS.
13. ALL PLANT MATERIAL SHALL BE INSTALLED IN ACCORDANCE WITH PLANTING DETAILS.
14. ALL PLANTING BEDS SHALL HAVE A MINIMUM 10" DEPTH OF PREPARED SOIL. WITH APPROVAL, EXISTING SOIL MAY BE UTILIZED PROVIDED THE PROPER SOIL AMENDMENTS ARE TILLED THOROUGHLY INTO THE TOP 10" OF SOIL. REFER TO SOIL PLACEMENT NOTES.
15. WHILE PLANTING TREES AND SHRUBS, BACKFILL ⅔ OF PLANTING HOLE AND WATER TREE THOROUGHLY BEFORE INSTALLING THE REMAINDER OF SOIL MIXTURE. AFTER ALL SOIL HAS BEEN PLACED INTO THE PLANTING HOLE WATER THOROUGHLY AGAIN.
16. THE CONTRACTOR MUST LABEL ALL TREES WITH THE COMMON AND BOTANICAL NAMES PRIOR TO FINAL INSPECTION.
17. OAK TREES SHALL BE TREATED FOR TWO-LINE CHESTNUT BORER BOTH AT THE TIME OF INSTALLATION AND DURING THE SECOND GROWING SEASON.
18. AREAS THAT CALL FOR STONE MULCH SHALL RECEIVE LANDSCAPE FABRIC WITH 3" DEEP, 3/4" ROUND RAPIDS STONE MULCH, REFER TO DETAIL (8). CONTRACTOR TO PROVIDE LANDSCAPE FABRIC AND MULCH SPECIFICATIONS TO LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION. LANDSCAPE FABRIC SHALL BE INSTALLED TO COVER THE ENTIRE AREA TO RECEIVE STONE MULCH WITH EACH SEAM OVERLAPPING A MINIMUM OF 6".
19. ALL AREAS WITH STONE MULCH SHALL HAVE A COMMERCIAL GRADE ALUMINUM EDGING INSTALLED TO SEPARATE STONE FROM ADJACENT LANDSCAPE. CONTRACTOR TO PROVIDE SPECIFICATIONS FOR COMMERCIAL GRADE ALUMINUM EDGING TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION. INSTALL PER MANUFACTURES INSTRUCTIONS.
20. ALL PLANTING BEDS NOT NOTED TO RECEIVE STONE MULCH SHALL BE MULCHED WITH 3" DEEP SHREDDED HARDWOOD MULCH, AND ALL TREES PLANTED IN TURF AREAS SHALL RECEIVE A 3" DEEP SHREDDED HARDWOOD MULCHED RING AS SHOWN IN PLANTING DETAILS.
21. ALL PLANTING BEDS AND TREE RINGS SHALL HAVE A 4" DEEP TRENCHED BED EDGE CREATED BY EITHER A FLAT LANDSCAPE SPADE OR MECHANICAL EDGER. BED EDGES ARE TO BE CUT CLEAN AND SMOOTH AS SHOWN ON LANDSCAPE PLANS WITH A CLEAN DEFINITION BETWEEN TURF AND PLANTING AREAS.
22. ALL TURF SEED AREAS SHALL RECEIVE A MINIMUM OF 6" DEPTH OF TOPSOIL. WITH APPROVAL, EXISTING SOIL MAY BE UTILIZED PROVIDED THE PROPER SOIL AMENDMENTS ARE TILLED THOROUGHLY INTO THE TOP 6" OF SOIL AS INDICATED IN THE SOIL PLACEMENT NOTES. REQUIRED AMENDMENTS SHALL BE DETERMINED BASED ON A SOIL ANALYSIS TO BE PERFORMED. ALL TOPSOIL AMENDMENT SHALL BE AGED WEED FREE MANURE OR CLASS 1 ORGANIC MATTER.
23. FOR LAWN SEEDING, APPLY A STARTER FERTILIZER AND SEED UNIFORMLY AT THE RATE RECOMMENDED BY MANUFACTURER, AND PROVIDE A MULCH COVERING THAT IS SUITABLE TO PROMOTE SEED GERMINATION AND TURF ESTABLISHMENT. CONTRACTOR TO PROVIDE FERTILIZER, SEED, AND MULCH SPECIFICATIONS TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION. EROSION CONTROL MEASURES ARE TO BE INSTALLED IN THOSE AREAS REQUIRING STABILIZATION (SWALES, SLOPES EXCEEDING 1:3, AND THOSE LOCATIONS INDICATED IN CIVIL DRAWINGS).
24. THE CONTRACTOR TO ENSURE A SMOOTH, UNIFORM QUALITY TURF IS ACHIEVED WITH NO BARE SPOTS LARGER THAN 6" X 6". ANY BARE SPOTS LARGER THAN 6" X6" AT THE END OF ESTABLISHMENT PERIOD SHALL BE RESEEDED AT THE CONTRACTORS EXPENSE TO OBTAIN A DENSE, UNIFORM LAWN.
25. ALL FINISH GRADING AND LAWN AREAS TO BE INSTALLED BY LANDSCAPE CONTRACTOR.
26. ALL DISTURBED AREAS WITHIN THE PROJECT SHALL BE RESTORED TO ORIGINAL OR BETTER CONDITION.
27. ALL DISTURBED AREAS OUTSIDE THE LIMITS OF WORK SHALL BE RESTORED TO ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE OWNER.
28. THE CONTRACTOR SHALL VERIFY ALL EXISTING UTILITIES, INCLUDING ANY IRRIGATION LINES, PRIOR TO DIGGING. CONSULT DIGGERS HOTLINE.
29. TREES SHALL BE INSTALLED NO CLOSER THAN:
    - -10 FEET FROM ANY FIRE HYDRANT
    - - 7 FEET FROM STORM SEWER, SANITARY SEWER LATERALS, AND WATER SERVICE
30. THE CONTRACTOR SHALL ENSURE THAT SOIL CONDITIONS AND COMPACTION ARE ADEQUATE TO ALLOW FOR PROPER DRAINAGE AROUND THE CONSTRUCTION SITE. UNDESIRABLE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING OF WORK. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE PROPER SURFACE AND SUBSURFACE DRAINAGE IN ALL AREAS
31. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS, FEES, AND LICENSES NECESSARY FOR THE INSTALLATION OF THIS PLAN.
32. THE CONTRACTOR IS TO REVIEW ALL SITE ENGINEERING DOCUMENTS PRIOR TO INSTALLATION. ANY CONFLICTS MUST BE REPORTED TO THE LANDSCAPE ARCHITECT. THESE LANDSCAPE DRAWINGS ARE FOR THE INSTALLATION OF PLANT MATERIALS ONLY UNLESS OTHERWISE STATED.
33. THE CONTRACTOR SHALL PROVIDE WATERING AND MAINTENANCE SERVICES FOR A PERIOD OF 60 DAYS TO ENSURE VEGETATIVE ESTABLISHMENT. UPON COMPLETION OF THE PROJECT, CONTRACTOR SHALL SUPPLY THE OWNER IN WRITING WITH ONGOING WATERING AND MAINTENANCE INSTRUCTIONS.
34. PLANT MATERIALS SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR FROM TIME OF OWNER ACCEPTANCE. ONLY ONE REPLACEMENT PER PLANT WILL BE REQUIRED DURING THE WARRANTY PERIOD EXCEPT IN THE EVENT OF FAILURE TO COMPLY WITH THE SPECIFIED REQUIREMENTS.
35. THE CONTRACTOR IS RESPONSIBLE TO CONDUCT A FINAL WALK THROUGH WITH THE LANDSCAPE ARCHITECT AND OR OWNERS REPRESENTATIVE TO ANSWER QUESTIONS, PROVIDE INSTRUCTIONS, AND ENSURE THAT PROJECT REQUIREMENTS HAVE BEEN MET.

SOIL PLACEMENT NOTES

1. LOOSEN SUBGRADE TO A MINIMUM DEPTH INDICATED IN PLANTING NOTES USING A CULTI-MULCHER OR SIMILAR EQUIPMENT, AND REMOVE STONES MEASURING OVER 1-1/2 INCHES IN ANY DIMENSION, STICKS, RUBBISH AND OTHER EXTRANEOUS MATTER. AREAS ADJACENT TO WALKS AND PAVEMENT SHALL BE FREE OF EXCESS STONE AND PAVING MATERIALS SO AS TO PROVIDE AN UNINTERRUPTED CROSS SECTION OF SOIL. INTERNAL PARKING ISLANDS SHALL BE LOOSENED TO A DEPTH OF 30".
2. THOROUGHLY BLEND PLANTING SOIL MIX FOR PLANTING BED AREAS. (1 PART EXISTING SOIL, 1 PART TOPSOIL, 1 PART ORGANIC SOIL AMENDMENT, 2.9 POUNDS PER CUBIC YARD OF 4-4-4 ANALYSIS SLOW-RELEASE FERTILIZER)
3. TREE AND SHRUB HOLES SHALL BE FILLED WITH A PREPARED PLANTING MIXTURE OF 1 PART TOPSOIL, 2 PARTS PLANTING SOIL MIX.
4. SPREAD SOIL AND SOIL AMENDMENTS TO DEPTH INDICATED ON DRAWINGS, BUT NOT LESS THAN REQUIRED TO MEET FINISH GRADES AFTER NATURAL SETTLEMENT. (FINISH GRADE OF PLANTING BEDS SHALL BE 3" BELOW ALL ADJACENT SURFACES. FINISH GRADE OF TURF SEEDING AREAS SHALL BE 1" BELOW ALL ADJACENT HARD SURFACES, WALKS, AND CURBS.)
5. PLACE APPROXIMATELY 1/2 OF TOTAL AMOUNT OF SOIL REQUIRED. WORK INTO TOP OF LOOSENED SUBGRADE TO CREATE A TRANSITION LAYER, THEN PLACE REMAINDER OF THE SOIL. SOIL TRANSITION LAYER SHALL BE TILLED TO A MINIMUM DEPTH OF 6" BELOW THE DEPTH OF NEWLY PLACED SOIL. PARKING LOT ISLANDS SHALL BE CROWNED TO A HEIGHT OF 6" TO PROVIDE PROPER DRAINAGE UNLESS OTHERWISE NOTED.
6. DO NOT SPREAD IF PLANTING SOIL OR SUBGRADE IS FROZEN, MUDDY, OR EXCESSIVELY WET.
7. FINISH GRADING: GRADE SOIL TO A SMOOTH, UNIFORM SURFACE PLANE WITH A LOOSE, UNIFORMLY FINE TEXTURE.
8. ROLL AND RAKE, REMOVE RIDGES, AND FILL DEPRESSIONS TO MEET FINISH GRADES.
9. RESTORE PLANTING BEDS IF ERODED OR OTHERWISE DISTURBED AFTER FINISH GRADING AND BEFORE PLANTING.



1 TREE PLANTING
1/4" = 1'-0" 329343-01



2 TREE PLANTING ON SLOPE
3/8" = 1'-0" 329343-02



3 EVERGREEN TREE PLANTING
1/4" = 1'-0" 329343-03



BAREROOT PLANTING NOTES:
1. SOAK ROOTS IN WATER FOR AT LEAST ONE HOUR BUT NOT MORE THAN 24 HOURS PRIOR TO PLANTING.
2. SCARIFY SIDES AND BOTTOMS OF HOLE.
3. PROCEED WITH CORRECTIVE PRUNING OF THE TOP AND BOTTOM ROOTS.
4. TRANSFER PLANT DIRECTLY FROM WATER TO HOLE. SET PLANT SO THE ROOT FLARE IS APPROXIMATELY AT THE FINISHED SOIL ELEVATION. SPREAD ROOTS OUT EVENLY, PLUMB AND IMMEDIATELY BACKFILL WITH PLANTING SOIL MIX.
5. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANTS AND FILL VOIDS.
6. BACKFILL VOIDS AND WATER SECOND TIME.
7. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.

4 SHRUB PLANTING
1/2" = 1'-0" 329333-02



5 PERENNIAL PLANTING
1" = 1'-0" 3293-01



(*) = SPECIFIED PLANT SPACING PER PLANTING LIST

6 PLANT SPACING
3/4" = 1'-0" 3293-02



7 TRENCHED BED EDGE
3/4" = 1'-0" 3293-03



8 STONE MAINTENANCE STRIP
3/4" = 1'-0" 329413-01

©2025 RINKA+
756 North Milwaukee Street, Suite 250
Milwaukee, Wisconsin 53202
p 414.431.8101

△ Revisions

NOT FOR CONSTRUCTION

W MITCHELL ST. & S 66TH ST.
WEST ALLIS, WI 53214

Date Issued: 08/29/2025

RINKA project #: 25074

Sheet Title

LANDSCAPE GENERAL NOTES & DETAILS

Sheet # L-2

Luminaire Schedule								
Label	**Qty**	**Arrangement**	**LLF**	**Tag**	**Description**	**Lum. Watts**	**Total Watts**	**Lum. Lumens**
B	5	SINGLE	0.950	KUZCO	EB3036-xx	11	55	562
EX	2	SINGLE	0.950	TBD	EXISTING CITY STREET LIGHTS TO REMAIN	53.6184	107.237	6918
OB4	9	SINGLE	0.950	LITHONIA	RADPT P3 xxK ASY (13FT POLE 2FT BASE) LIGHT POLE	53.6184	482.566	6918
W1	8	SINGLE	0.950	LITHONIA	WPX1 LED P1 xxK MVOLT WALLPACK	11.47	91.76	1568

Calculation Summary							
Label	**CalcType**	**Units**	**Avg**	**Max**	**Min**	**Avg/Min**	**Max/Min**
SITE	Illuminance	Fc	0.77	6.1	0.0	N.A.	N.A.
PARKING	Illuminance	Fc	1.92	4.30	0.50	3.84	8.60

WEST LAPHAM
(60' R.O.W.)

SOUTH 66TH STREET
(60' R.O.W.)

EXIST WYE CONNECTION
INV=120.75 ± (10" N)
INV=120.75 ± (10" S)
INV=120.43 (6" W)

38.2 LF @ 6" SDR-35 SANITARY LATERAL @ 1.0%

ADJUST EXISTING CONCRETE APRON FOR NEW LOCATION PER CITY STANDARDS.

CONNECT TO EXISTING CATCH BASIN
IE @ 123.10

PROPERTY LINE

EXISTING SIDEWALK

EX
MH: 15

EXIST 6" WATER LATERAL
WM INV= 123.00 (6")

EXIST 6" SANITARY STUB
INV=121.18 (6")
SAN LATERAL MAY HAVE TO BE ENLARGED TO ACCOMMODATE PROPOSED FLOWS FROM BUILDING. COORDINATE WITH PLUMBER.

PROPOSED 6" STORM SEWER

PROPOSED TRENCH DRAIN

CONCRETE RETAINING WALL AND STEPS. SEE ARCHITECTURAL & STRUCTURAL PLANS

W1
MH: 9

RETAIL
FF = 134.0

PROPOSED BUILDING
FF = 137.0

BUILDING OVERHANG

SIDEWALK BY OTHERS

CONCRETE PATIO

LIGHT DUTY PAVEMENT BY OTHERS

BIKE PARKING (4)

OB4
MH: 15

B
MH: 3

ADA SIGN POST

OUTDOOR SPA

18" CURB & GUTTER

ADA PARKING STALL

PROPOSED TRANSFORMER

CLUBHOUSE
FF = 137.0

6' WIDE CONC WALK

PATIO

PROPERTY LINE TO BE ADJUSTED TO MATCH PROPOSED BUILDING REQUIREMENTS

PROPOSED 8" STORM SEWER

PARKING EASEMENT

CONNECT TO EX 15" @ STO @ IE = 127.26 W/ NEW CB RIM 131.7

NEW CB
RIM 130.5

APPROXIMATE LOCATION OF PREVIOUSLY INSTALLED UTILITIES

STORM SEWER EASEMENT

EXISTING 15" STORM STUB

CONFIRM BUILDING DOES NOT IMPACT FIBER OPTIC OR RELOCATE UTILITY IF IN CONFLICT

ENTERPRISE
Lighting & Control

#	DATE	COMMENTS

REVISIONS

DRAWN BY : LB

DATE : SEPT 02, 2025

SCALE : 1/16" = 1'-0"

SONA LOT 3

WEST ALLIS, WISCONSIN

SITE LIGHTING