

Qualitywork@actesllc.com



# A Custom To, LLC

Roofing, Siding, Windows, Gutters, Attic Insulation & Venting Solutions

## Proposal

<b>Customer</b>	Kyle Ehler	<b>Date</b>	10-14-20
<b>Address</b>	1100 S. 65 <sup>th</sup> St.	<b>Roof</b>	No
<b>City/ST</b>	West Allis, WI.	<b>Gutters</b>	No
<b>Phone</b>	414-377-5859	<b>Siding</b>	As Listed
<b>Fax</b>	N/A	<b>Other</b>	No
<b>Attention</b>	Lokedogg4@gamil.com	<b>Inspector</b>	Keith

**Scope of Work:**

**Tear Off & New Vinyl Siding Install on North and Northeast Corner of House Only : (does not include roof dormer)**  
**Please remove items from walls that could move or fall when pounding nails to secure siding.**

- Tear off existing layer of vinyl siding and dispose of all debris into dumpster provided by contractor.
- Install new 3/8" thick fan fold insulation.
- Install insulation tape at all seams and around all windows and penetrations.
- Install new starter strip.
- Install new metal drip caps above windows and doors.
- Install new outside & inside corners.
- Install new J-channel.
- Install new Single 8", Mastic brand vinyl siding. (color – white)
- Install utility trim below all window J's and horizontally below soffit J's.
- All accessories are used in accordance with manufactures standards and don't affect the overall proposed price. Accessories to include light blocks, split minis and dryer vent caps.

         **\$6,390.00**

**Price: Includes Material & Labor**

**As Listed Above.**  
 Please initial by any work you wish to have performed.

Payable upon completion of work.  
 Please read terms and agreement section before signing proposal.

**Warranty Information:**





ESTIMATE  
HEATH SWANSON 414-712-8397

12200 West Adler Lane  
West Allis, WI 53214  
(414) 543-0929  
www.WeatherProExteriors.com

## SIDING WORK ORDER AND ADDENDUM

Customer: KYLE EHLERT No. of Days: \_\_\_\_\_ Job #: \_\_\_\_\_  
 Address: 1100 S. 65th ST Hm: \_\_\_\_\_ Measured By: \_\_\_\_\_  
 City: WEST ALLIS State: WI Zip: \_\_\_\_\_ Wk: \_\_\_\_\_ Sales Rep: HEATH SWANSON  
 E-mail: \_\_\_\_\_ Cell: \_\_\_\_\_ Best Time to Call: \_\_\_\_\_  
 Roof Pitch: \_\_\_\_\_ No. of stories: 1 House Type: 2 STORY Dumpster Location: STREET

PRODUCT	COLOR	DESCRIPTION / LOCATION
<b>WeatherPro Siding</b> <input type="checkbox"/> Structure <input checked="" type="checkbox"/> Quest <input type="checkbox"/> Board & Batten <input type="checkbox"/> Cedar Discovery <input type="checkbox"/> LP Smartside <input type="checkbox"/> _____ <input type="checkbox"/> DL-4.5" <input type="checkbox"/> T-5" <input type="checkbox"/> D-4" <input type="checkbox"/> D-7" <input type="checkbox"/> D-5" <input type="checkbox"/> Hand Split <input type="checkbox"/> D-6" <input type="checkbox"/> Half Round <input type="checkbox"/> S-7" <input checked="" type="checkbox"/> 8" SMOOTH	WHITE	<del>ADULT SIDE</del> FACING W WASHINGTON ST
Tyvek Included <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	N/A	
Tear Off Old Siding <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	N/A	
Fan Fold Insulation Included <input type="checkbox"/> Yes <input type="checkbox"/> No	N/A	
<b>Corners</b> <input checked="" type="checkbox"/> T5 <input type="checkbox"/> LS <input type="checkbox"/> W4 <input type="checkbox"/> F5 <input type="checkbox"/> C <input type="checkbox"/> W3 <input type="checkbox"/> FLS <input type="checkbox"/> B <input type="checkbox"/> M4 <input type="checkbox"/> _____		
<b>Soffit</b> <input type="checkbox"/> Aluminum <input type="checkbox"/> D6 <input type="checkbox"/> Continuous Vent <input type="checkbox"/> T4		
<b>Fascia, Frieze, and Beams</b> <input type="checkbox"/> Fascia <input type="checkbox"/> Beams *Posts can't be trimmed		
<b>Gutters and Downspouts</b> <input type="checkbox"/> New 5" Seamless / 4" Downs <input type="checkbox"/> Existing placement <input type="checkbox"/> Change Placement	N/A	
<b>Gutter Protection</b> <input type="checkbox"/> Gutter Protection (see drawing) <input checked="" type="checkbox"/> Not Included		
<b>Window, Door, and Garage Door Trim</b> <input type="checkbox"/> Aluminum <input type="checkbox"/> 3 1/2" Vinyl Lineal <input type="checkbox"/> Smooth <input type="checkbox"/> PVC Textured		
<b>Shutters</b> <input type="checkbox"/> Panel / Panel <input type="checkbox"/> Louvered / Louvered		
<b>Installation</b> <input type="checkbox"/> Replace Gable Vents <input type="checkbox"/> Replace Rotted Wood (see description and drawing) <input type="checkbox"/> Remove and Replace Awnings <input type="checkbox"/> Fascia Build Out		

NOTES:  
 FRONT SIDE FOR ADDITIONAL  
 \$1225 WITH 15% TALL SPECIAL  
 TOTAL FOR BOTH SIDES = \$5535  
 FOR 8" SMOOTH  
 ON SIDE OF HOUSE  
 \$5071 - 15% = \$4310

DRAWING:

I hereby agree that the above listed options are correct. Only work as stated above, on the retail contract or other official addendums will be honored. Oral or implied representations are not recognized. Any requests for additional labor and/or materials are at an additional charge. Pre-existing conditions such as rotted wood, insect infestation, code violations, etc. unknown to us at time of sale or commencement may require additional labor and materials at an additional charge, payable upon substantial completion. WeatherPro Exteriors will remove siding when structurally allowed; however, if existing structure does not have proper backing, the new siding will be installed over existing siding. Due to existing conditions beyond our control, repairs on existing leaky gutters can be attempted but cannot be guaranteed.

Customer: \_\_\_\_\_ Date: \_\_\_\_\_ Customer: \_\_\_\_\_ Date: \_\_\_\_\_