For: City of West Allis / Att: Brett **Monday, August 3, 2026**
Quoted By: Donnie
Universal Truck Eq.

VENDOR: UNIVERSAL TRUCK EQUIPMENT
CONTACT PERSON: DONNIE BJORGE
ADDRESS: N15921 SCHUBERT RD., GALESVILLE, WI 54630
PHONE NO.: 608-539-4600
E-MAIL ADDRESS: donnie@universaltruckequipment.com

Summary Page: MN DOT Contract # 267382

Total Plow Price: $17,259.00 **Color Std. Orange**
(Freight is NOT included in Total Plow Price) (Customer Pick Up)
(Freight Charge Est. Only if UTE delivers to the City...$950/Per Plow

Estimated Lead Time is Approx. 240-270 Days After Received Purchase Order

Please note:
Because of the new emissions on trucks, Universal Truck Equipment will not be held responsible for major modifications or relocation of the exhaust. The truck should be ordered to accommodate the equipment you a putting on the truck, Universal Truck Equipment should not be held responsible for major modifications or the relocation of air tanks, battery boxes, exhaust and/or fuel tanks. Each truck mfg./salesman has different ways setting up patrol trucks, it is important to get things in the right location. Because we are not directly involved ordering the truck we have know way of knowing what kind of modifications or relocations need to be done, if (unless we are aware of it before the equipment is bided). Most of the time the trucks can be ordered to elimin minimize the modifying or relocating of the standard truck exhaust, battery boxes, air tanks and/or fuel tanks.

Price quote for	**6.0 NON MnDOT PRICE SCHEDULE - FRONT SNOW PLOW**		
Vendor Name:	**Universal Truck Equipment Inc.**		
Contact Person	**Donnie Bjorge**		
Street Address	**N15921 Schubert Rd.**		
P.O. Box:			
City, State, Zip	**Galesville, WI 54630**		
Phone #:	**608-539-4600**		
Toll Free #:			
Fax #:	**608-539-4800**		
Email Address	**donnie@universaltruckequipment.com**		
	Information Requested	Answer	
	Plow Type (one way, reversable, high wing, v plow, etc)		
6.00	Two-Way Reversible Snow Plow - Make and Model	**Universal CST-11-43L two way power reversible snow plow, moldboard trip type, 11' plow length. Note: plow portion of Loop hitch is standard (see options for other plow hitches).**	
6.00	Moldboard Height	**43" (measured with 6" cutting edge)**	
	Moldboard Smoothed Rolled Design include Radius.	**Multiple radius's 15 to 20**	
	Discharge Height	**43" (measured with 6" cutting edge)**	
	Plow Throat depth from vertical to deepest point in.	**14-1/2"**	
	Moldboard thickness & type of steel	**10ga. moldboard thickness, grade 50 Hi-tensile steel. Plow is fully welded**	
	Type, size and number of vertical reinforcement ribs.	**Eight (8) 1/2" flame cut ribs, ribs are 100% fully welded**	
	Adjustable cutting edge angles to pavement measured from roadway surface through perpendicular back toward truck.	**Adjustable angles, 20, 10 & 15 degrees**	
	State number of hook up points from moldboard to frame.	**Six (6)**	
	Type and size of reinforcement of frog at either end.	**3/4" x 4" x 4" lower angle, fully gusseted (carbide punched)**	
	Type and size of circle frame	**Semi-circle type, constructed with 1/2" x 3-1/2" x 3-1/2" rolled angle**	
	Size of double acting reversing cylinders.	**Two heavy duty 4" x 10" power reversing cylinders with 2" Nitrided rods. Cylinders are mounted above the push frame.**	
	Size and type of reinforced snow flap	**3-ply, 1/2" thick x 12" wide**	
	Type and size of push frame	**Push frame is constructed with 3/8" x 4" x 4" x 102" square tubing**	
	Carbide cutting Edge (AASHTO punched) size.	**5/8" x 8" x (length of plow) steel cutting edge is standard (see options for carbide)**	
	Distance beyond vertical that snow deflectors integral with moldboard extends.	**27"**	
	Size of Adjustable Snow Shoes	**None - See Options Includes adjustable parking stand**	
	Weight of plow (less hitch and hydraulics)	**2,240 lbs.**	
	Type and number of resettable HD compression spring trip	**Two (2) heavy duty moldboard trip springs, compression type, made of 9/16" wire**	
	Painting system with type of paint	**Primed & Painted Std. Black (See options for different colors)**	
	Warranty Information	**One Year Warranty, parts and labor**	
	Volume Discounts	**N/A**	
	TOTAL PRICE:	**$9,705**	
	Front Plow Options		
6.01	12' plow length in lieu of 11'		$270
6.02	48" plow height in lieu of 43"		$626
6.03	52" plow height in lieu of 43"		$1,605
6.04	**Std. UTE Orange painted plow in lieu of std. black (All Plow Models & Sizes) (#IG4241040)**		**$212**
6.05	Std. UTE Yellow painted plow in lieu of std. black (All Plow Models & Sizes) (#4421)		$379
6.06	Std. UTE Red painted plow in lieu of std. black (All Plow Models & Sizes) (#2303)		$310
6.07	Plow end markers, red cable type, 27", installed (set)		$100

6.08	Adjustable mushroom type shoes- std. pad, 12" round x 2" thick (installed with standard shoe brackets)	$1,805
6.09	Adjustable mushroom type shoes- Ni-Hard pad, 12" round x 2" thick (installed with standard shoe brackets)	$2,481
6.10	Adjustable shoes- Flat type shoe pad (installed with standard shoe brackets)	$1,678
6.11	**Curb shoe, (2" cold rolled round), installed ($188 each x 2)**	**$376**
6.12	Plow cutting edge shoe, installed (each)	$348
6.13	Trip cutting edge, one piece or split, in lieu of moldboard trip	$1,773
6.14	**Moldboard trip/trip edge combo, in lieu of moldboard trip only**	**$2,929**
6.15	**Individually replaceable trip edge springs ilo standard**	**$623**
6.16	**3/4" x 6" carbide cutting edge with cover blade in lieu of std. ($145 per ft. ~ see Surcharge)**	**$1,595**
6.17	Sabre Shielded Carbide cutting edge blades 3/4" x 6" ilo std. ("No" cover blade required) (per ft.)	$267
6.18	Flex Pro (Joma) cutting edge blades 3/4" x 6" ilo std. (Includes cover bar) (per ft.)	$200
6.19	Flex Pro (Joma) backer blades for additional support (per ft.)	$44
6.20	Stucchi Multifaster coupler with parking station (coupling under pressure)	$1,630
6.21	Plow portion of 29" Husting hitch in lieu of Loop Hitch	$1,567
6.22	Plow portion of 34" Husting hitch in lieu of Loop Hitch	$1,814
6.23	Roller Kit for 29" or 34" Husting hitch, installed on plow only	$635
6.24	Plow portion of Snap Link hitch in lieu of Loop Hitch	$828
6.25	Plow portion of Universal Pin hitch (Falls #46) in lieu of Loop Hitch	$193
6.26	Level lift assy. for Universal Pin hitch	$326
6.27	**40" plow height w/ in lieu of 43" height (deduct)**	**($351)**
6.28	**Mailbox/Guard rail corner cut (per side)**	**$458**
6.29	Three piece trip cutting edge in lieu of std. 2-piece trip cutting edge	$180
6.30	UTE Frog Saver- Installed (helps prevent wearing into the lower angle) (Each)	$253
6.31	3/4" x 4" x 4" lower trip edge angle in lieu of std. 1/2" x 3" x 4"	$178
6.32	"J" Type moldboard curl in lieu of "C" type curl	$275
6.33	Heavy Duty Pushframe (10-Ribs, 8-Pivot Points, 126" wide pushframe) ILO Std.	$910
6.34	3/16" moldboard thickness in lieu of std. 10ga.	$404
6.35	Bolt-On Plow Air Foil (Bolts to top of moldboard ribs)	$3,280
6.36	**Poly Moldbaord Plow in lieu of steel moldboard (2-extra ribs/10 total)**	**$724**
Misc.	**Carbide Surcharge ($82/ft.) & 1/2" P70 chain ILO std.**	**$988**
Misc.	**Custom Parking Stand in lieu of std. & Deduct std. short hose kit**	**$0**
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	**$5.50**
	Delivery Starting Point City, State, & Zip:	**N15921 Schubert Rd., Galesville, WI 54630**
	Body Shop Rate	**$140**
	Mechanic Shop Rate	**$140**

TOTAL PLOW PRICE (Each): **$17,259**

Freight is NOT included

Sales tax is NOT included